

Section 211.06—Testing is amended to replace the third paragraph with the following:

Abson recovery samples shall be PG graded according to the requirements of AASHTO M 320-05. Samples meeting the required grades specified in Section 211.01 of the Specifications shall be acceptable.

9-24-07, Reissued 7-2008 (SPCN)

(c223ag1-0309) **SECTION 223 STEEL REINFORCEMENT** of the Specifications is amended to add the following:

(e) **Corrosion Resistant Reinforcement** shall conform to the requirements of one of the following standards:

- ASTM A1035/A1035M – Standard Specification for Deformed and Plain, Low-carbon, Chromium, Steel Bars for Concrete Reinforcement.
- ASTM A955/A955M - Standard and Specification for Deformed and Plain Stainless Steel Bars for Concrete Reinforcement. UNS* Designations: S24100, S30400, S31603, S31653, S32101, S32201, S32205

* Unified Numbering System for Metals and Alloys

2-19-09 (SPCN)

(c302h00-0708) **SECTION 302.03(b) PRECAST DRAINAGE STRUCTURES** of the Specifications is amended to include the following:

Precast units, excluding concrete pipe, prestressed concrete items and soundwalls, conforming to the requirements herein will only be accepted under a Quality Control/Quality Acceptance Program (QC/QA). The Contractor shall have the producer perform quality control functions in accordance with a Department approved QC/QA plan. Each piece, manufactured under the QC/QA program, in addition to the date and other required markings, shall be stamped with the letters (QC), as evidence that the required QC/QA procedures have been performed. Each shipping document shall be affixed with the following:

We certify that these materials have been tested and conform to VDOT Precast Concrete Products Quality Assurance Program

Signature and Title

1-14-08 (SPCN)